



e-ISSN 3083-6018

SOCIAL DEVELOPMENT: Economic and Legal Issues

<https://www.eu-scientists.com/index.php/sdel>



Innovative Construction Project Management Techniques for Urban Infrastructure Development

Yaroslav Dolia  ¹*

¹ Odesa State Academy of Civil Engineering and Architecture (Ukraine). Owner of Dom-D Construction LLC, Master's Degree in Construction Engineering.

* **Corresponding Author**, e-mail: ayaroslavdolia@ukr.net

ARTICLE INFO

Research Article

DOI:

[10.70651/3083-6018/2026.6.25](https://doi.org/10.70651/3083-6018/2026.6.25)

Received:

21 April 2026

Accepted:

22 May 2026

Published online:

24 May 2026

Copyright © 2026 by authors



This is an open access journal and all published articles are licensed under a Creative Commons Attribution—NonCommercial 4.0 International (CC BY-NC 4.0)



ABSTRACT

Urban infrastructure development continues to be constrained by cost overruns, schedule delays, fragmented stakeholder coordination, and rising sustainability requirements. This paper examines innovative construction project management (CPM) techniques – digital twins, Building Information Modeling (BIM), Internet of Things (IoT) site monitoring, artificial-intelligence-assisted scheduling, agile delivery methods, and prefabricated/modular construction – as mechanisms for improving coordination systems, workflow optimization, and strategic planning on large-scale urban and infrastructure projects. Drawing on a synthesis of twenty-five peer-reviewed sources together with practitioner experience in delivering prefabricated Glued-Laminated-Timber (Glulam) housing in the United States, the paper proposes an Integrated Off-Site-On-Site Coordination (IOOC) framework that links early digital design coordination, off-site manufacturing scheduling, and real-time on-site monitoring into a single management cycle. The framework addresses three recurring gaps identified in the literature: fragmentation between design and manufacturing, weak stakeholder alignment, and underuse of real-time data for adaptive scheduling. Findings indicate that projects combining BIM-enabled coordination with modular production and IoT-based tracking achieve shorter, more predictable delivery than conventional sequential models. The paper concludes that the convergence of digital coordination tools and off-site manufacturing is a scalable route to addressing housing shortages and infrastructure backlogs while reducing environmental impact.

KEYWORDS

construction project management, urban infrastructure development, prefabricated construction, Building Information Modeling (BIM), coordination systems, workflow optimization, modular housing delivery.



e-ISSN 3083-6018

СОЦІАЛЬНИЙ РОЗВИТОК: економіко-правові проблеми

<https://www.eu-scientists.com/index.php/sdel>




Інноваційні методи управління будівельними проектами для розвитку міської інфраструктури

Ярослав Доля  ¹*

¹ Одеська державна академія будівництва та архітектури (Україна). Власник Dom-D Construction LLC, магістр, інженер-будівельник.

* Автор-кореспондент, e-mail: ayaroslavdolia@ukr.net

СТАТТЯ	АНОТАЦІЯ
Дослідницька DOI: 10.70651/3083-6018/2026.6.25 Отримана: 21.04.2026 р. Прийнята: 22.05.2026 р. Опублікована: 24.05.2026 р. Авторське право © 2026 авторів  Цей твір ліцензовано на умовах Ліцензії Creative Commons «Із Зазначенням Авторства – Некомерційна 4.0 Міжнародна» (CC BY-NC 4.0). 	Розвиток міської інфраструктури продовжує стримуватися перевитратами коштів, затримками графіків, фрагментованою координацією зацікавлених сторін та зростанням вимог до сталого розвитку. У цій статті розглядаються інноваційні методи управління будівельними проектами (CPM) – цифрові двійники, інформаційне моделювання будівель (BIM), моніторинг об'єктів за допомогою Інтернету речей (IoT), планування за допомогою штучного інтелекту, гнучкі методи реалізації та збірне/модульне будівництво – як механізми для покращення систем координації, оптимізації робочих процесів та стратегічного планування великомасштабних міських та інфраструктурних проєктів. Спираючись на синтез двадцяти п'яти рецензованих джерел разом із досвідом практиків у сфері будівництва збірних будинків з клеєної деревини (Glulam) у Сполучених Штатах, у статті пропонується інтегрована система координації поза об'єктом та на місці (IOOC), яка поєднує ранню координацію цифрового проєктування, планування виробництва поза об'єктом та моніторинг на місці в режимі реального часу в єдиний цикл управління. Ця структура враховує три повторювані прогалини, виявлені в літературі: фрагментацію між проєктуванням та виробництвом, слабку узгодженість зацікавлених сторін та недостатнє використання даних у режимі реального часу для адаптивного планування. Результати дослідження показують, що проєкти, що поєднують координацію на основі BIM з модульним виробництвом та відстеженням на основі Інтернету речей, досягають коротших та більш передбачуваних термінів виконання, ніж традиційні послідовні моделі. У статті робиться висновок, що конвергенція інструментів цифрової координації з позамайданчиковим виробництвом є масштабним шляхом до вирішення проблем дефіциту житла та затримок у веденні інфраструктури, одночасно зменшуючи вплив на навколишнє середовище. КЛЮЧОВІ СЛОВА управління будівельними проектами, розвиток міської інфраструктури, збірне будівництво, інформаційне моделювання будівель (BIM), системи координації, оптимізація робочих процесів, будівництво модульного житла.

1. Introduction

Urban populations continue to expand faster than the infrastructure and housing stock available to support them, and construction organizations are increasingly asked to deliver more within tighter budgets and shorter timelines. At the same time, traditional, sequential delivery models in which design, procurement, and on-site construction proceed largely in series remain vulnerable to the cost and schedule overruns that are repeatedly documented in infrastructure and housing projects worldwide [3; 14]. Megaprojects in particular are prone to optimism bias, weak governance structures, and value that is captured unevenly among stakeholders, which further undermines predictability [11; 18].

Two forces are reshaping how urban infrastructure and housing projects are managed. First, digital technologies BIM, digital twins, IoT sensing, and AI-assisted scheduling are giving project managers far greater visibility into design conflicts, resource use, and site conditions than was previously possible [2; 6; 19; 21]. Second, off-site and modular delivery models are decoupling manufacturing from weather-, labor-, and site-dependent construction sequences, compressing timelines and improving quality control [5; 12; 23; 25]. Individually, each of these techniques has been shown to improve some dimension of project performance. However, the literature also shows that their benefits are frequently constrained by fragmentation: digital models are not consistently linked to manufacturing schedules, and site data is not consistently fed back into planning decisions [9; 17].

This paper has three objectives. First, it synthesizes the current literature on coordination systems, workflow optimization, and strategic planning techniques relevant to urban infrastructure and construction project management. Second, it proposes an integrative framework, the Integrated Off-Site–On-Site Coordination (IOOC) framework, that connects digital design coordination, off-site manufacturing, and site-level monitoring into a continuous management cycle rather than three disconnected functions. Third, it evaluates the framework against practitioner experience delivering prefabricated Glulam housing near New York City, illustrating how the framework applies to a real, scalable construction operation. The paper proceeds with a literature review, a description of the methodology used to develop the framework, findings, a discussion of implications, and conclusions.

2. Literature Review

2.1. Stakeholder Coordination and Risk

Effective coordination among owners, designers, contractors, and regulators is consistently identified as a determinant of project performance. Abdillah and Amin found that stakeholder engagement and the balance of influence among dominant stakeholders directly shape project performance outcomes, indicating that coordination structures, not only technical planning, determine delivery success [1]. Xia, Guo, and Lin similarly show that construction contractors' risk exposure is closely tied to how stakeholder attributes are managed, and propose that structured stakeholder-attribute analysis can materially reduce project risk [24]. Irfan et al. extend this argument to the public sector, demonstrating that project planning quality and project manager competencies jointly predict public infrastructure project success, suggesting that coordination capability is as important as planning documentation itself [13].

2.2. Digital Coordination Technologies: BIM and Digital Twins

BIM has become a central coordination technology in construction. Du shows that BIM-based engineering project management improves information sharing and reduces design conflicts relative to conventional 2D-drawing-based coordination [9]. Rui, Yaik-Wah, and Cher Siang similarly document BIM's role in improving scheduling accuracy and reducing rework across the project lifecycle [21]. Zhang et al., reviewing BIM applications specifically for prefabricated construction, find that BIM is particularly valuable where design and manufacturing must be tightly synchronized, since geometric and scheduling errors that would otherwise surface on site can be identified during the design stage [25]. Cao, Kamaruzzaman, and Aziz extend this to green building delivery, finding that BIM utilization supports both technical coordination and sustainability performance tracking [4].

Digital twins represent a further extension of BIM into operational and urban-scale coordination. Al-Sehrawy, Kumar, and Watson propose a classification system for digital twin use in urban planning

and city infrastructure management, distinguishing between twins used for design coordination and those used for ongoing operational monitoring [2]. Chia Lai et al. describe an urban digital-twin architecture intended to support sustainable smart-city planning, highlighting the technical and organizational challenges of scaling twin-based coordination beyond a single project [6]. Mazzetto's review of urban digital twin integration finds that while adoption is accelerating, interoperability between twin platforms and on-the-ground project management systems remains a persistent barrier [19] – a gap directly relevant to the coordination framework proposed later in this paper.

2.3. IoT-Enabled Site Monitoring

IoT technologies extend digital coordination from the design stage into live site conditions. Khan et al. find that IoT-based monitoring systems measurably improve safety outcomes and operational efficiency on construction sites by providing real-time visibility into equipment, materials, and worker location [15]. This literature indicates that IoT's contribution to project management is greatest when sensor data is actively integrated into scheduling and decision-making rather than used solely for passive monitoring.

2.4. Prefabrication, Modularization, and Lean Delivery

Prefabricated and modular construction methods are widely associated with reduced timelines and improved cost predictability. Chauhan et al. find that prefabrication's monetary and non-monetary benefits are strongly moderated by product modularity highly modular systems capture greater benefits than partially prefabricated ones [5]. Wuni, Shen, and Osei-Kyei identify critical success criteria for prefabricated, prefabricated volumetric construction projects, emphasizing early supply-chain integration and design standardization as primary success drivers [23]. Ifionu et al. review the cost efficiency and scalability of modular construction specifically in relation to housing shortages, concluding that modular delivery can meaningfully expand housing supply where manufacturing capacity is systematically scaled [12]. Garcés et al. systematic review of Lean Construction principles reinforces this, finding that waste-reduction and flow-based scheduling techniques compound the benefits of prefabrication when applied together rather than independently [10].

2.5. Agile and AI-Enabled Project Management

Agile methods, long associated with software development, are increasingly applied to construction. Dong et al., following a systematic review, propose a construction-specific definition of agile project management centered on iterative planning and adaptive response to changing site conditions [8]. Kineber et al. identify critical success factors for agile project management in sustainable residential construction, finding that iterative design review cycles are especially valuable in prefabricated delivery models where design changes are costly to implement after manufacturing begins [16]. Lappalainen et al. describe a broader transformation of construction project management toward "situational awareness," in which real-time data and adaptive planning replace static, schedule-based planning [17].

Artificial intelligence is emerging as a complementary tool. Mali et al. compare predictive AI/machine-learning models for construction project management and find that AI-assisted forecasting improves schedule and cost prediction accuracy relative to conventional estimating methods [20]. Salimimoghadam et al. systematic review of AI in project management identifies data availability and organizational readiness — not algorithmic capability — as the primary barriers to adoption [22]. Coelho et al. offer a complementary efficiency-measurement approach, applying data envelopment analysis to benchmark project management performance, which the framework proposed in this paper adapts as a performance-tracking mechanism [7].

2.6. Governance, Cost Overruns, and Megaproject Delivery

Finally, the literature on cost overruns underscores why coordination and workflow techniques matter. Belay documents systemic cost overruns and schedule delays across infrastructure projects in low-income economies, tracing much of the variance to weak planning and coordination rather than technical failure alone [3]. Julca-Varas et al. similarly identify primary risk factors for delays and cost overruns in water-supply infrastructure projects in Peru, again pointing to planning and stakeholder-coordination failures as leading causes [14]. Lovallo, Flyvbjerg, and Cristofaro propose a three-stage governance process for large projects intended to counteract these tendencies through structured

decision gates [18], and Gil's theoretical work on megaprojects frames these overruns as a purpose-and-value-distribution problem, not merely a scheduling one [11]. Together, this literature establishes that coordination systems, workflow optimization, and strategic planning are not peripheral improvements to construction project management – they are the central mechanisms through which cost and schedule performance are actually determined.

3. Problem Statement

The main problem addressed in this study is the persistent fragmentation of construction project management processes, which limits effective coordination among digital design, off-site manufacturing, and on-site implementation in urban infrastructure development.

4. Methods and Materials

This paper adopts a qualitative, framework-development methodology combining (a) a structured synthesis of the twenty-five sources reviewed above and (b) reflective analysis of practitioner experience delivering prefabricated Glulam residential construction near New York City. The literature was reviewed thematically across five categories corresponding to the sub-sections above: stakeholder coordination, digital coordination technologies, IoT-enabled monitoring, prefabrication/modularization, and agile/AI-enabled planning. For each category, recurring success factors and recurring failure modes were extracted and compared across sources to identify where the literature converges and where gaps remain unaddressed.

The practitioner reflection component draws on direct involvement in two completed residential projects that integrated off-site Glulam component manufacturing with on-site assembly and U.S. building-code compliance. This experience was used not as a data source to be statistically analyzed, but as a validation lens: each proposed component of the framework was checked against whether it addressed a coordination failure actually observed during project delivery for example, misalignment between manufacturing lead times and on-site assembly crews, or delays in translating design changes into updated production schedules.

The resulting Integrated Off-Site–On-Site Coordination (IOOC) framework was then constructed by mapping the recurring success factors from the literature synthesis onto the three phases common to prefabricated construction delivery digital design coordination, off-site manufacturing, and on-site assembly/monitoring and by specifying the coordination mechanism (tool, data flow, and decision gate) that connects each phase to the next. This approach is consistent with the analytical, practice-oriented purpose of the paper. Rather than reproducing existing literature reviews, it translates the literature's findings into an applied management framework and evaluates that framework's plausibility against direct project experience.

5. Results

The literature synthesis and practitioner validation converge on three findings.

Firstly, digital coordination technologies (BIM, digital twins) most reliably improve project performance when they are treated as shared coordination infrastructure across organizational boundaries, rather than as a design-stage tool used only by the design team [2; 9; 19; 21; 25]. Where BIM models are not actively shared with manufacturing and site teams, the coordination benefit documented in the literature does not fully materialize.

Secondly, prefabrication and modularization deliver their strongest benefits when paired with structured supply-chain and workflow planning rather than used in isolation [5; 10; 12; 23]. This confirms that workflow optimization is not a byproduct of prefabrication but a precondition for realizing its benefits.

Thirdly, real-time data from IoT sensors, AI-assisted forecasting, and situational-awareness scheduling adds the greatest value when it feeds back into active decision-making rather than passive reporting [15; 16; 17; 20; 22].

Table 1 compares conventional sequential delivery with the integrated delivery model supported by the literature reviewed above.

Table 1. Conventional vs. Integrated (Off-Site/On-Site) Construction Delivery

Dimension	Conventional Sequential Delivery	Integrated Off-Site–On-Site Delivery
Design–manufacturing link	Largely sequential; design finalized before manufacturing begins	Concurrent, BIM-linked design and manufacturing scheduling [9; 25]
Stakeholder coordination	Ad hoc, meeting-driven	Structured, data-shared coordination gates [1; 13; 24]
Schedule visibility	Static baseline schedule	Real-time, IoT/AI-informed schedule updates [15; 17; 20]
Quality control	Primarily on-site inspection	Factory-controlled component QC plus on-site verification [5; 23]
Typical exposure to overrun	High, per infrastructure cost-overrun literature [3; 14]	Reduced through earlier risk identification [11; 18]

Source: Formed by the author.

Table 2 sets out the components of the proposed IOOC framework, described further in the Discussion.


Table 2. Integrated Off-Site–On-Site Coordination (IOOC) Framework — Core Components

Phase	Primary Coordination Mechanism	Literature Basis
Digital Design Coordination	Shared BIM model with manufacturing-ready component library	[4; 9; 21; 25]
Off-Site Manufacturing Scheduling	Production schedule linked to BIM change log; lean flow scheduling	[5; 10; 12; 23]
On-Site Assembly & Monitoring	IoT-tracked delivery/assembly status feeding back into schedule and BIM model	[15; 16; 17]
Cross-Phase Governance	Stakeholder decision gates at each phase transition; AI-assisted forecasting for risk flags	[1; 13; 18; 20; 22; 24]

Source: Compiled by the author.

6. Discussion

The findings above point toward a specific coordination problem that the existing literature identifies but does not fully resolve: digital design tools, off-site manufacturing systems, and on-site monitoring technologies are each well studied individually, yet they are rarely analyzed as a single, continuous management cycle. Mazzetto explicitly identifies interoperability between digital coordination platforms and ground-level project management as an open challenge [19], and Lappalainen et al. account of the shift toward “situational awareness” implies exactly this kind of continuous data flow, without specifying how off-site manufacturing should be incorporated into it [17]. The IOOC framework proposed in this paper is intended to close that gap directly (See Figure 1).

**Figure 1. Digital Construction Workflow with Feedback Loops**

Source: Built by the author.

In Phase 1, the framework requires that the BIM model used for design coordination be built directly from a manufacturing-ready component library, so that structural members – such as Glulam beams, panelized wall systems, and roof trusses – are modeled as the actual manufactured units rather

than as generic geometry. This directly operationalizes the finding from Zhang et al. and Rui et al. that BIM's coordination value in prefabricated construction depends on tight synchronization between design geometry and manufacturing output [21; 25]. In the practitioner's own Glulam operation, the absence of this synchronization in early projects produced avoidable rework when panel dimensions modeled at the design stage required field modification during assembly – precisely the failure mode the framework is designed to eliminate.

In Phase 2, off-site manufacturing scheduling is linked directly to the BIM change log rather than managed as a separate production plan. Every design revision automatically flags affected production batches, and lean, flow-based scheduling principles are applied to sequence manufacturing around assembly-crew availability rather than production-line convenience alone, thereby decreasing the timeline [5; 10; 23] (See Figure 2). This addresses the finding from Chauhan et al. that prefabrication's benefits scale with modularity and structured planning, not with off-site manufacturing alone [5].




Figure 2. Comparative Construction Delivery Timeline Chart

Source: Built by the author.

In Phase 3, on-site assembly is tracked using IoT-enabled status updates – component delivery, installation completion, and inspection sign-off – that feed back into both the production schedule (Phase 2) and the BIM model (Phase 1), rather than being recorded solely for after-the-fact reporting. This reflects the finding from Khan et al. and Kineber et al. that real-time data delivers its greatest value when it actively informs decisions rather than passively documenting them [15; 16].

Underlying all three phases is a cross-phase governance layer, in which stakeholder decision gates – informed by AI-assisted forecasting of schedule and cost risk – occur at each phase transition rather than only at traditional project milestones. This addresses the stakeholder-coordination and governance findings from Abdillah and Amin, Irfan et al., Lovallo et al., and Xia et al., who each identify structured stakeholder engagement, rather than technology alone, as the determinant of whether coordination benefits are actually realized [1; 13; 18; 24].

Applied to the proposed Glulam housing operation, the IOOC framework provides a direct operational template for scaling from two completed projects to approximately one hundred homes annually. At that scale, the coordination failures documented in the megaproject and cost-overrun literature – optimism bias, weak decision gates, and fragmented stakeholder communication [3; 11; 14; 18] – become materially more consequential than they are on a single project, because delays or design errors propagate across multiple simultaneous production batches rather than remaining isolated. The framework's cross-phase governance layer is specifically intended to prevent this propagation by surfacing risk flags – schedule slippage in manufacturing, unresolved design changes, site-readiness delays – before they compound.

More broadly, the framework contributes to urban infrastructure practice by offering a management structure, rather than a technology list, for coordinating design, manufacturing, and assembly at scale. This addresses a structural gap: existing literature evaluates BIM, IoT, prefabrication, and AI forecasting largely as separate interventions, whereas the housing-shortage and infrastructure-delivery challenges facing U.S. cities require these interventions to function as one coordinated system across the full delivery cycle, from design through occupancy (See Figure 3).

The framework's principal limitation is that it has been validated against a single practitioner's project experience rather than a broader empirical sample; formal testing across multiple prefabricated construction operations would strengthen confidence in its generalizability. Its intended contribution is therefore best understood as a structured, literature-grounded hypothesis for how off-site and on-site

construction management can be integrated – one directly actionable within the proposed Glulam operation and potentially transferable to other prefabricated infrastructure and housing delivery models.




Figure 3. BIM Data Flow Architecture for Construction Management

Source: Built by the author.

7. Conclusions

This paper has reviewed innovative construction project management techniques relevant to urban infrastructure and housing delivery, spanning stakeholder coordination, digital design tools, IoT-enabled monitoring, prefabrication, and AI-assisted planning. The literature converges on a consistent conclusion: these techniques improve project performance most reliably when integrated into a continuous coordination cycle rather than applied as isolated interventions. Building on this synthesis, the paper proposes the Integrated Off-Site–On-Site Coordination (IOOC) framework, which links digital design coordination, off-site manufacturing scheduling, and on-site assembly monitoring through a shared data model and structured stakeholder governance. Evaluated against practitioner experience in prefabricated Glulam housing delivery, the framework offers a scalable, actionable structure for expanding modular housing production while addressing the coordination failures most commonly associated with cost overruns and schedule delays in urban infrastructure projects. As U.S. cities continue to face housing shortages alongside pressure to reduce construction’s environmental footprint, integrated coordination frameworks of this kind represent a practical and generalizable contribution to construction project management practice.

References

1. Abdillah, M. R., & Amin, M. (2022). Analysis of the influence of stakeholder domination, engagement, and organizational behavior on project performance. *International Journal of Research and Review*, 9(2), 82–93. <https://doi.org/10.52403/ijrr.20220212>
2. Al-Sehrawy, R., Kumar, B., & Watson, R. (2021). A digital twin use classification system for urban planning & city infrastructure management. *Journal of Information Technology in Construction*, (26), 832–862. <https://doi.org/10.36680/JITCON.2021.045>
3. Belay, M. S., Tilahun, S., Yehualaw, M., Matos, J., Sousa, H., & Workneh, E. T. (2021). Analysis of cost overrun and schedule delays of infrastructure projects in low income economies: case studies in Ethiopia. *Advances in Civil Engineering*, (1), 4991204. <https://doi.org/10.1155/2021/4991204>
4. Cao, Y., Kamaruzzaman, S. N., & Aziz, N. M. (2022). Green building construction: A systematic review of BIM utilization. *Buildings*, 12(8), 1205. <https://doi.org/10.3390/buildings12081205>
5. Chauhan, K., Peltokorpi, A., Lavikka, R., & Seppänen, O. (2022). The monetary and non-monetary impacts of prefabrication on construction: The effects of product modularity. *Buildings*, 12(4), 459. <https://doi.org/10.3390/buildings12040459>
6. Lai, C. C., Sarkar, A., Dinh, P. A., Gaikwad, S., & Hsu, C. H. (2024, December). Urban digital-twin planning for sustainable smart cities: System architecture, preliminary experiments, and open challenges. In *Proceedings*

- of the 2nd International Workshop on Middleware for Digital Twins (pp. 7-12). <https://doi.org/10.1145/3702636.3703443>
7. Coelho, M. B., Lacerda, D. P., Piran, F. A. S., Silva, D. O. D., & Sellitto, M. A. (2024). Project management efficiency measurement with data envelopment analysis: A case in a petrochemical company. *Applied System Innovation*, 7(1). <https://doi.org/10.3390/asi7010002>
 8. Dong, H., Dacre, N., Baxter, D., & Ceylan, S. (2024). What is agile project management? Developing a new definition following a systematic literature review. *Project Management Journal*, 55(6). <https://doi.org/10.1177/87569728241254095>
 9. Du, X. (2021). Research on engineering project management method based on BIM technology. *Scientific Programming*, (1), 7230585. <https://doi.org/10.1155/2021/7230585>
 10. Garcés, G., Forcael, E., Osorio, C., Castañeda, K., & Sánchez, O. (2025). Systematic review of Lean Construction: an approach to sustainability and efficiency in construction management. *Journal of Infrastructure Preservation and Resilience*, 6(1), 1-28. <https://doi.org/10.1186/s43065-025-00119-1>
 11. Gil, N. (2022). Megaprojects: A meandering journey towards a theory of purpose, value creation and value distribution. *Construction Management and Economics*, 40(7-8), 562-584. <https://doi.org/10.1080/01446193.2021.1946832>
 12. Ifionu, E. S., Njemanze, E. C., Enabulele, A. B. O., Okparabenyo, E., & Egbubine, L. (2026). Cost efficiency and scalability of modular construction: A systematic and bibliometric review of its role in addressing housing shortages. *Journal of Management, and Development Research*, 3(1), 61-70. <https://doi.org/10.69739/jmdr.v3i1.1854>
 13. Irfan, M., Khan, S. Z., Hassan, N., Hassan, M., Habib, M., Khan, S., & Khan, H. H. (2021). Role of project planning and project manager competencies on public sector project success. *Sustainability*, 13(3), 1421. <https://doi.org/10.3390/su13031421>
 14. Julca-Varas, C., García-Segura, T., Torres-Machí, C., & Montalbán-Domingo, L. (2025). Primary risks for delays and cost overruns in the construction of drinking water supply and sanitation projects in Peru. *Journal of Management in Engineering*, 41(3), 1-13. <https://doi.org/10.1061/JMENEA.MEENG-6496>
 15. Khan, A. M., Alrasheed, K. A., Waqar, A., Almujiabah, H., & Benjeddou, O. (2024). Internet of things (IoT) for safety and efficiency in construction building site operations. *Scientific Reports*, (14), 28914. <https://doi.org/10.1038/s41598-024-78931-0>
 16. Kineber, A. F., Oke, A. E., Elshaboury, N., Abunada, Z., Elseknidy, M., Zamil, A., Alhusban, M., & Ilori, S. A. (2024). Agile project management for sustainable residential construction: A study of critical success factors. *Frontiers in Built Environment*, (10), Article 1442184. <https://doi.org/10.3389/fbuil.2024.1442184>
 17. Lappalainen, E. M., Seppänen, O., Peltokorpi, A., & Singh, V. (2021). Transformation of construction project management toward situational awareness. *Engineering, Construction and Architectural Management*, 28(8), 2199-2221. <https://doi.org/10.1108/ECAM-12-2020-1053>
 18. Lovallo, D., Flyvbjerg, B., & Cristofaro, M. (2023). Governing large projects: A three-stage process to get it right. *Academy of Management Perspectives*, 37(2). <https://doi.org/10.5465/amp.2021.0129>
 19. Mali, A. S., Kolhe, A., Gorde, P., Kolekar, A., Umbrajkar, A., Solepatil, S., & Zare, K. (2025). Application of artificial intelligence and machine learning in construction project management: a comparative study of predictive models. *Asian Journal of Civil Engineering*, 26(6), 2671-2686. <https://doi.org/10.1007/s42107-025-01335-6>
 20. Mazzetto, S. (2024). A review of urban digital twins' integration, challenges, and future directions in smart city development. *Sustainability*, 16(19), 8337. <https://doi.org/10.3390/su16198337>
 21. Rui, Y., Yaik-Wah, L., & Cher Siang, T. (2021). Construction project management based on building information modeling (BIM). *Civil Engineering and Architecture*, 9(6), 2055-2061. <https://doi.org/10.13189/cea.2021.090633>
 22. Salimimoghadam, S., Ghanbaripour, A. N., Tumpa, R. J., Kamel Rahimi, A., Golmoradi, M., Rashidian, S., & Skitmore, M. (2025). The rise of artificial intelligence in project management: A systematic literature review of current opportunities, enablers, and barriers. *Buildings*, 15(7), 1130. <https://doi.org/10.3390/buildings15071130>
 23. Wuni, I. Y., Shen, G. Q., & Osei-Kyei, R. (2021). Evaluating the critical success criteria for prefabricated prefinished volumetric construction projects. *Journal of Financial Management of Property and Construction*, 26(2), 279-297. <https://doi.org/10.1108/JFMP-03-2020-0013>
 24. Xia, N., Guo, J., & Lin, Y.-H. (2021). Managing stakeholder attributes for risk mitigation: Evidence from construction project contractors. *International Journal of Managing Projects in Business*, 14(7), 1605-1625. <https://doi.org/10.1108/IJMPB-11-2020-0345>
 25. Zhang, S., Li, Z., Li, T., & Yuan, M. (2021). A holistic literature review of building information modeling for prefabricated construction. *Journal of Civil Engineering and Management*, 27(7), 485-499. <https://doi.org/10.3846/jcem.2021.15600>